



Precast concrete leach drain manufacturers known to the DOH in WA

The *Health (Treatment of Sewage and Disposal of Effluent and Liquid Waste) Regulation 1974* requires precast concrete leach drains to be approved by the Executive Director, Public Health. The following table details the specifications of precast concrete leach drains approved for use in Western Australia for the onsite disposal of wastewater.

| Manufacturer | Infiltrative Area m ² /m | Module Length m |
|------------------------------------|--|--------------------|
| Altham Plumbing Contractors | 1.94 | 0.9 |
| Australind Premix Concrete | 1.4 | 1.5 |
| Avon Septics and Backhoe Hire | 1.91 | 1.5 |
| B.Co Rural | 1.535 | 1 |
| Bunbury Cement Products | 1.91 | 1.335 |
| Bunbury Modular Brick | 1.48 | 1.5 |
| Busselton Cement Products | 1.81 | 1.2 |
| C & BJs Concrete Supplies | 2.06 | 1.86 |
| Collie Steel Supplies | 2 | 1.5 |
| Concrete Products Esperance | 1.59 | 1.52 |
| Concrete World Esperance | 1.686 | 1.5 |
| Coopers Concrete Products | 1.6 | 1.5 |
| Dalwallinu Concrete Works | 1.51 | 1.2 |
| Galvin Concrete & Sheetmetal | 1.58 | 1.2 |
| GNC Concrete & Precast (Geraldton) | 1.43 | 1.2 |
| Hester Concrete Products | 1.45 | 1.4 |

| Manufacturer | Infiltrative Area m²/m | Module Length m |
|--|--|----------------------------|
| Hills Concrete Products (Northam) | 1.58 | 1.2 |
| Jandakot Cement Works | 1.44 | 1.2 |
| Kimberley Septics | 1.33 | 1 |
| Kondinin Concrete Products | 1.82 | 1 |
| LAB Concrete | 1.81 | 1.2 |
| L & B Concrete | 1.81 | 1.2 |
| Maddington Concrete Products | 1.8 | 1.2 |
| Manjimup Concrete Manufacturers | 1.7 | 1.2 |
| Margaret River Modules | 1.82 | 1.8 |
| Midland Cement Products | 1.61 | 1.2 |
| Moora Concrete Works | 1.8 | 1.2 |
| Mundaring Concrete | 1.9 | 1.2 |
| Naval Base Concrete | 1.65 | 1 |
| PN & ER Newman's Quality Concrete Products | 1.82 | 1.2 |
| Podmore Holdings Pty Ltd | 1.85 | 1.2 |
| Regal Precast Concrete Products | 1.78 | 1.21 |
| Thompson Building Industries | 1.975 | 1.5 |
| Toodyay Septics & Backhoe Hire | 1.94 | 2.35 |
| TUSS Precast Concrete | 1.71 | 1.21 |
| UDUC Concrete Products | 1.74 | 2.4 |
| Vanmaris Concrete Products | 1.6 | 2 |
| | 1.7 | 1 |
| Wheatbelt Concrete Products | 1.68 | 1.2 |
| | 1.45 | 2.4 |
| | 1.67 | 3 |

| Manufacturer | Infiltrative Area m ² /m | Module Length m |
|-----------------------|--|--------------------|
| Winchester Industries | 1.82 | 1.5 |
| Yuella Fabrications | 1.73 | 1 |

More Information:

Water Unit

Environmental Health Directorate
Department of Health
PO Box 8172
PERTH BUSINESS CENTRE WA 6849

Telephone: 08 9388 4999

Facsimile: 08 9388 4910

This document is available in alternative formats on request for a person with a disability.